### **SEPT Thermal Vacuum Test Plan**

Doc. No.: STEREO-ETKI-006

**Compiled by:** Reinhold Mueller-Mellin, University of Kiel

Ludovic Duvet, ESTEC

Last change: 14-FEB-2004

# 1 Scope

This document specifies the qualification thermal vacuum tests to be performed on the SEPT units. The TV tests to be performed include

TV cycling

- Temperature-time bake-out
- Thermal balance
- Bake-out certification

Thermal balance and bake-out certification information is not given in this document and is TBS after consultation with GSFC.

Successful completion of the TV tests is part of the unit-level qualification tests required to fly the four SEPT units on the two spacecraft of the NASA STEREO mission. The qualification test requirements for STEREO instruments are specified in **AD 1**. The instrument environmental test plan is described in **AD 3**.

# 1.1 Scope of the document

The scope of the document is to define

- the test objectives
- the specimen and test configurations
- the test specifications
- the measurement point plan
- the test procedure

# 1.2 Test objectives

- Verification of general build quality and structural integrity after thermal cycling
- Verification of expected in-orbit temperatures
- Verification of compliance with cleanliness requirements

# 2 Applicable Documents

- **AD 1** STEREO Environment Definition, Observatory, Component and Instrument Test Requirements Document, Doc. No. 7381-9003
- AD 2 STEREO Contamination Control Plan, Doc. No. 7381-9006
- AD 3 IMPACT Environmental Test Plan, Version D 2003-Dec-30
- AD 4 IMPACT Contamination Control Plan, Version A 2003-May-14

## 3 List of Abbreviations

EM Engineering Model FM1. FM2 Flight Model 1. 2

FTIR Fourier Transform Infrared Spectrometer

GN<sub>2</sub> Dry nitrogen gas IPA Isopropanol

LIVAF Little Vacuum Facility, ESTEC

MLI Multi-layer Insulation NVR Non-volatile Residue

SEPT-E Solar Electron and Proton Telescope – Ecliptic SEPT-NS Solar Electron and Proton Telescope – North-South

S/C Spacecraft TBS To be supplied

### 4 Cleanliness

Cleanliness of the test environment is of major importance for two reasons:

 SEPT sensors are equipped with contamination sensitive silicon semiconductor detectors of the ion-implanted type. Molecular and particulate contaminants must be avoided.

 Other payload instruments on board of STEREO are equipped with highly sensitive optical surfaces and detectors. Cross contamination must be avoided.

Contamination control shall adhere to the STEREO Contamination Control Plan in **AD 2**. The instrument contamination control plan is described in **AD 4**. Contamination control during TV must be achieved for two reasons:

- Certify that the TV chamber itself is not a significant source of contamination.
- Give evidence that SEPT itself is not a significant source of contamination.

The LIVAF is not equipped with cryo pumps, but with a combination of primary rotary forepump and secondary turbo-molecular pump. In order to certify the chamber, a measurement of the residual gas composition is carried out as well as a NVR swab analysis with FTIR.

To ensure that SEPT itself is not a source of contamination, a materials list is compiled and reviewed, material data sheets are provided and samples are submitted for analysis where available data was insufficient. Non-flight items like special vacuum harness will be baked out separately prior to testing with SEPT.

Allowed cleaning agents are methanol and ethanol. Use of isopropanol (IPA) close to SEPT is allowed provided that GN<sub>2</sub> purge is applied to the SEPT sensor.

#### 4.1 Environmental conditions at ambient pressure:

Cleanliness: Class III (10<sup>5</sup> particles/ft<sup>3</sup>)

when not purged and not in class III clean environment, unit shall

be bagged

Temperature: 20 °C +- 3 °C Relative humidity: 50 % +- 10 %

#### 4.2 Environmental conditions after pump-down:

Pressure:  $1 \times 10^{-5}$  torr (0.0013 Pa) or less

Temperature: constrained by sensor, applicable thermistor channel:

SEPT-E S/C TEMP and TEMP RTN, connector J2, pin 25 /26 and SEPT-NS S/C TEMP and TEMP RTN, connector J2, pin 25/26

high temperature limit at +50 °C +-1 °C low temperature limit at -40 °C +- 1 °C

Contamination:

contaminants will be trapped by a cold finger. During transitions from cold to hot, SEPT shall not stay colder than surrounding to prevent deposition of contaminants (slow transition, when warming up, shroud temperature lags thermal plate temperature). Backfilling the chamber for re-pressurization will be with  $GN_2$ .

# 5 Specimen and test configuration

SEPT consists of two units (SEPT-E and SEPT-NS) per spacecraft, four units in total:

S/C	Instrument Component	Part #
Ahead	SEPT-E	A195 SN1
Ahead	SEPT-NS	A201 SN2
Behind	SEPT-E	A195 SN3
Behind	SEPT-NS	A201 SN4

The four flight units are structurally identical to the EM, which was not subjected to qualification tests, though. The two SEPT-E units are mounted thermally isolated to the S/C +Y panel, the two SEPT-NS units are mounted thermally isolated to their brackets on the S/C +Z panel.

#### 5.1 Test constraints

The four SEPT units will be subjected to a thermal vacuum test program in the Little Vacuum Facility (LIVAF) of the Mechanical Systems Laboratory, ESTEC Test Centre, in week 10 and 11, 2004. At this time, procurement of thermal hardware is not yet complete, missing items are thermostats, film heaters, flight MLI blankets. Hence the thermal balance test will be a separate test to be performed at GSFC after final installation of the thermal hardware.


The four SEPT units shall undergo 6 powered operational cycles, 1 survival cycle. To reduce test costs, two SEPT units (SEPT-E and SEPT-NS) are TV cycled together, resulting in two test runs (FM1 and FM2).

To quickly achieve thermal equilibrium, SEPT-E and SEPT-NS are mounted directly to the temperature controlled plate, i.e. without brackets and thermal isolators (Ultem).

Actuation of SEPT cover release shall be exercised in hot and cold soak. As doors are opened by onetime actuators which require manual restow, 2 (out of 4) doors per unit will be opened at cold soak, the other 2 at hot soak.

#### 5.2 Test set-up

Two SEPT units are mounted side by side on a thermal plate (length 500 mm, width 285 mm, see Fig. below). Each unit is fixed by four M4 screws (torque 2.6 Nm) to the temperature controlled plate. Aluminium washers (2 mm thick) under the mounting lugs provide clearance for thermocouples on the bottom lid.




# 5.3 Test equipment

The TV test will be performed in the Little Vacuum Facility (LIVAF) of the Mechanical Systems Laboratory, ESTEC Test Centre. The pumping system of the facility consists of a combination of primary rotary forepump (pump speed  $40 \text{ m}^3/\text{h}$ ) and secondary turbo-molecular pump (pump speed 600 l/s). The turbo-molecular pump is connected to the vacuum vessel with in-between a gate valve. Vacuum level:  $< 10^{-5}$  mbar, pump-down time:  $\sim 8$  hours.

The facility is equipped with a shroud (door, horizontal cylinder, back). The emissivity of the shroud is  $\epsilon$  = 0.88. The nominal temperature range of the shroud is -180 °C to +80 °C. There is a cold trap at -80 °C between specimen and pump exit.

#### 5.4 Test harness





#### 5.5 Test levels

The temperatures of the following table are based on the thermal analysis by the IMPACT thermal engineer John Hawk/GSFC. As the SEPT TV test precedes the thermal balance test (see test constraints above), the thermal model is not yet verified. Hence the qualification temperatures must include a 10 °C margin to the max and min predicted operating temperatures.

Unit	Operating	Survival	Qualification
SEPT-E [°C]	-30 to +40	-40 to +50	-40 to +50
SEPT-NS [°C]	-30 to +40	-40 to +50	-40 to +50

# 5.5.1 Definition of temperature limits

TNO-MAX	Non-operating temperature	+50 °C
TO-MAX	Operating temperature	+50 °C
TNO-MIN	Non-operating temperature	- 40 °C
TSU-MIN	Cold startup temperature	- 40 °C
TO-MIN	Operating temperature	- 40 °C

## 5.5.2 Transition rates and stability criteria

The maximum rate of temperature change is 3 °C/min. Care must be exercised not to overshoot TNO-MAX or undershoot TNO-MIN. Temperature stability is achieved when the temperature is within 3 °C of the plateau and the rate of change is less than 1 °C/hour.

## 5.6 Definition of temperature measurement points

Control Temperature	thermocouple on thermal p	plate located between SEPT-E and


SEPT-NS

Reference Temperature 2 thermocouples on bottom lid of E-box, one per unit 2 thermocouples on sensor close to detectors, one per unit

Sensor temperature SEPT-E
Sensor temperature SEPT-NS
Sensor temperature SEP

# 5.7 Test Sequence

The SEPT thermal vacuum test sequence is given in the figures below which are taken from AD 1.



See Table 2.3-1 for component dependant test temperatures. Stabilization Criteria: Within 3°C Of Plateau And Changing < 1°C/Hr

See Fig 2.3.3.2-2 and -3 for detailed hot and cold transition definitions, resp.

Stabilize, Print T/C's, Soak 1Hour and Test Concurrently, Print T/C's

Six Operational Cycles Required

2 = Stabilize, Turn On, Soak 1Hour and Test Concurrently, Print T/C's at End of Soak

Figure 3.3.2.1-1 Typical Spacecraft Component Thermal Vacuum Profile




Figure 3.3.2.1-2 Detailed Hot Transition Definition




Figure 3.3.2.1-3 Detailed Cold Transition Definition

# **6** Test Procedure

### Caution:

SEPT uses high voltage (-80 V). Do not power SEPT unless the pressure is at ambient or below 10<sup>-3</sup> torr. Should the pressure unexpectedly rise while SEPT is powered (e.g. leak) use SEPT emergency switch-off.

# 6.1 Step-by-step sequence:

(time TBC by facility responsible):

Step	Cycle #	Time	Plate temperature	Activity
1	0	T0 - 100 h	+80 °C	Pressure < 10 <sup>-5</sup> torr. Start CDE by ramping LIVAF w/mechanical support equipment from RT to 80 °C, bake out for 48 h
2	0	T0 - 52 h	+60 °C	Return to RT, re-pressurize, install electrical support equipment, ramp to TNO-MAX + 10 °C, bake out for 48 h
3	0	T0 - 4 h	RT	Return to RT, re-pressurize, install FM1, turn on FM1, perform CPT prior to TV, turn off FM1, close chamber
4	1	T0	RT	Start pump-down to < 10 <sup>-5</sup> torr.
5	1	T0 + 4 h	+50 °C	Start hot ramp
6	1	T0 + 8 h	+50 °C	Hot soak (survival), at end of hot soak turn-on FM1, run nominal mode for 10 minutes, turn FM1 off
7	1	T0 + 9 h	-40 °C	Start cold ramp
8	1	T0 + 10 h	-40 °C	Cold soak (survival)
9	2	T0 + 11 h	+50 °C	Start hot ramp
10	2	T0 + 12 h	+50 °C	Hot soak, turn on FM1, CPT
11	2	T0 + 13 h	-40 °C	Start cold ramp
12	2	T0 + 14 h	-40 °C	Turn off FM1, cold soak, cold start-up FM1, CPT
13	3	T0 + 15 h	+50 °C	Start hot ramp
14	3	T0 + 16 h	+50 °C	Hot soak, CPT
15	3	T0 + 17 h	-40 °C	Start cold ramp
16	3	T0 + 18 h	-40 °C	Cold soak, CPT
17	4	T0 + 19 h	+50 °C	Start hot ramp
18	4	T0 + 20 h	+50 °C	Hot soak, CPT
19	4	T0 +	-40 °C	Start cold ramp

20         4         T0 + 22 h         -40 °C         Cold soak, CPT           21         5         T0 + 23 h         +50 °C         Start hot ramp           22         5         T0 + 24 h         +50 °C         Hot soak, CPT           23         5         T0 + 24 h         -40 °C         Start cold ramp           24         5         T0 + 26 h         -40 °C         Cold soak, CPT           25         6         T0 + 450 °C         Start hot ramp           26         6         T0 + 50 °C         Hot soak, CPT, open front doors SEPT-E, open rear doors SEPT-E, open rear doors SEPT-NS           27         6         T0 + 40 °C         Start cold ramp           28         6         T0 + 40 °C         Cold soak, CPT, open rear doors SEPT-E, open front doors SEPT-NS           29         7         T0 + 50 °C         Start hot ramp           30         7         T0 + 50 °C         Start hot ramp           31         7         T0 + 40 °C         Start cold ramp           31         7         T0 + 40 °C         Start cold ramp           32         h         T0 + 40 °C         Start cold ramp           33         T0 + 34 h         T0 + 50 °C         Start cold ramp           3			21 h		
22 h	20	4		-40 °C	Cold soak, CPT
23 h			-		
23 h	21	5		+50 °C	Start hot ramp
24 h   25   T0 + 40 °C   Start cold ramp			23 h		· ·
23         5         T0 + 25 h         -40 °C         Start cold ramp           24         5         T0 + 26 h         -40 °C         Cold soak, CPT           25         6         T0 + 27 h         +50 °C         Start hot ramp           26         6         T0 + 50 °C         Hot soak, CPT, open front doors SEPT-E, open rear doors SEPT-S           27         6         T0 + 40 °C         Start cold ramp           28         6         T0 + 40 °C         Cold soak, CPT, open rear doors SEPT-E, open front doors SEPT-NS           29         7         T0 + 50 °C         Start hot ramp           30         7         T0 + 50 °C         Start hot ramp           31         7         T0 + 40 °C         Start cold ramp           32         7         T0 + 40 °C         Start cold ramp           33 h         T0 + 33 h         T0 + 40 °C         Turn off FM1, cold soak, turn on FM1, CPT           33         T0 + 50 °C         Start hot ramp           34         T0 + 36 h         +50 °C         Temperature-time bake-out for 48 h           36         T0 + 84 h         Turn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM1           36         T0 + RT         End test	22	5	T0 +	+50 °C	Hot soak, CPT
25 h			24 h		
24         5         T0 + 26 h         -40 °C         Cold soak, CPT           25         6         T0 + 27 h         +50 °C         Start hot ramp           26         6         T0 + 28 h         +50 °C         Hot soak, CPT, open front doors SEPT-E, open rear doors SEPT-NS           27         6         T0 + 29 h         -40 °C         Start cold ramp           28         6         T0 + 29 h         -40 °C         Cold soak, CPT, open rear doors SEPT-E, open front doors SEPT-NS           29         7         T0 + 30 h         +50 °C         Start hot ramp           30         7         T0 + 50 °C         Turn off FM1, hot soak, turn on FM1, CPT           31         7         T0 + 32 h         -40 °C         Start cold ramp           32         7         T0 + 34 h         -40 °C         Start cold ramp           33         T0 + 34 h         -40 °C         Start cold ramp           34         T0 + 35 °C         Start hot ramp           35         T0 + 50 °C         Start hot ramp           35         T0 + 450 °C         Temperature-time bake-out for 48 h           36         T0 + 87         Turn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM1	23	5	T0 +	-40 °C	Start cold ramp
26 h   27 h   +50 °C   Start hot ramp			25 h		
25         6         T0 + 27 h         +50 °C         Start hot ramp           26         6         T0 + 28 h         +50 °C         Hot soak, CPT, open front doors SEPT-E, open rear doors SEPT-NS           27         6         T0 + 29 h         -40 °C         Start cold ramp           28         6         T0 + 30 h         -40 °C         Cold soak, CPT, open rear doors SEPT-E, open front doors SEPT-NS           29         7         T0 + 50 °C         Start hot ramp           30         7         T0 + 50 °C         Turn off FM1, hot soak, turn on FM1, CPT           31         7         T0 + 32 h         Start cold ramp           32         7         T0 + -40 °C         Start cold ramp           32         7         T0 + -40 °C         Turn off FM1, cold soak, turn on FM1, CPT           33         T0 + -40 °C         Start hot ramp           34         T0 + -40 °C         Start hot ramp           35         T0 + -40 °C         Temperature-time bake-out for 48 h           36         T0 + -84         Turn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM1           36         T0 + RT         End test FM1	24	5	T0 +	-40 °C	Cold soak, CPT
27 h  26			26 h		
26         6         T0 + 28 h         +50 °C         Hot soak, CPT, open front doors SEPT-E, open rear doors SEPT-NS           27         6         T0 + 29 h         -40 °C         Start cold ramp           28         6         T0 + 30 h         -40 °C         Cold soak, CPT, open rear doors SEPT-E, open front doors SEPT-NS           29         7         T0 + 50 °C         Start hot ramp           30         7         T0 + 50 °C         Turn off FM1, hot soak, turn on FM1, CPT           31         7         T0 + -40 °C         Start cold ramp           32         7         T0 + -40 °C         Turn off FM1, cold soak, turn on FM1, CPT           33         T0 + -50 °C         Start hot ramp           34         T0 + -50 °C         Start hot ramp           35         T0 +	25	6	-	+50 °C	Start hot ramp
28 h					
27         6         T0 + 29 h         -40 °C         Start cold ramp           28         6         T0 + 30 h         -40 °C         Cold soak, CPT, open rear doors SEPT-E, open front doors SEPT-NS           29         7         T0 + 50 °C         Start hot ramp           30         7         T0 + 50 °C         Turn off FM1, hot soak, turn on FM1, CPT           31         7         T0 + 32 h         -40 °C         Start cold ramp           32         7         T0 + 34 h         -40 °C         Turn off FM1, cold soak, turn on FM1, CPT           34         T0 + 35 h         +50 °C         Start hot ramp           34         T0 + 36 h         +50 °C         Temperature-time bake-out for 48 h           35         T0 + 87 h         RT         Turn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM1           36         T0 + RT         End test FM1	26	6	_	+50 °C	
28       6       T0 +					
28         6         T0 + 30 h         -40 °C         Cold soak, CPT, open rear doors SEPT-E, open front doors SEPT-NS           29         7         T0 + 50 °C         Start hot ramp           30         7         T0 + 50 °C         Turn off FM1, hot soak, turn on FM1, CPT           31         7         T0 + -40 °C         Start cold ramp           33 h         T0 + -40 °C         Turn off FM1, cold soak, turn on FM1, CPT           34 h         T0 + +50 °C         Start hot ramp           35         T0 + 34 h         T0 + 50 °C         Temperature-time bake-out for 48 h           35         T0 + 84         Turn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM1           36         T0 + RT         End test FM1	27	6	_	-40 °C	Start cold ramp
30 h   front doors SEPT-NS					
29         7         T0 + 31 h         +50 °C         Start hot ramp           30         7         T0 + 32 h         +50 °C         Turn off FM1, hot soak, turn on FM1, CPT           31         7         T0 + 33 h         -40 °C         Start cold ramp           32         7         T0 + -40 °C         Turn off FM1, cold soak, turn on FM1, CPT           34 h         T0 + +50 °C         Start hot ramp           35         T0 + 36         +50 °C         Temperature-time bake-out for 48 h           35         T0 + 84         RT         Turn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM1           36         T0 + RT         End test FM1	28	6	_	-40 °C	
31 h					
307T0 + 32 h+50 °CTurn off FM1, hot soak, turn on FM1, CPT317T0 + 33 h-40 °CStart cold ramp327T0 + 34 h-40 °CTurn off FM1, cold soak, turn on FM1, CPT33T0 + 35+50 °CStart hot ramp34T0 + 36+50 °CTemperature-time bake-out for 48 h35T0 + 84RTTurn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM136T0 +RTEnd test FM1	29	7	-	+50 °C	Start hot ramp
31       7       T0 + 33 h       -40 °C       Start cold ramp         32       7       T0 + -40 °C       Turn off FM1, cold soak, turn on FM1, CPT         34 h       T0 + +50 °C       Start hot ramp         35       T0 + +50 °C       Temperature-time bake-out for 48 h         36       T0 + 84       Turn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM1         36       T0 + RT       End test FM1	00			. 50 00	T (SEMALL ) SEMALORY
317T0 + 33 h-40 °CStart cold ramp327T0 + 34 h-40 °CTurn off FM1, cold soak, turn on FM1, CPT33T0 + 35+50 °CStart hot ramp34T0 + 36+50 °CTemperature-time bake-out for 48 h35T0 + 84RTTurn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM136T0 +RTEnd test FM1	30	/	_	+50 °C	Turn off FM1, not soak, turn on FM1, CP1
33 h  32 7 T0 + -40 °C Turn off FM1, cold soak, turn on FM1, CPT  34 h  35 Start hot ramp  36 T0 + FT Turn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM1  End test FM1	0.4	-		40.00	Otant and many
327T0 + 34 h-40 °CTurn off FM1, cold soak, turn on FM1, CPT33T0 + 35+50 °CStart hot ramp34T0 + 36+50 °CTemperature-time bake-out for 48 h35T0 + 84RTTurn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM136T0 +RTEnd test FM1	31	/		-40 °C	Start cold ramp
34 h  T0 + +50 °C Start hot ramp  35 T0 + +50 °C Temperature-time bake-out for 48 h  36 T0 + RT Turn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM1  Turn off FM1, verify doors are open, remove FM1  End test FM1	22	7		40 °C	Turn off FM1 and analy turn on FM1 CDT
33 T0 +	32	/		- <del>4</del> 0 C	Turn on Fivi i, cold soak, turn on Fivi i, CP i
35  T0 + +50 °C Temperature-time bake-out for 48 h 36  T0 + RT Turn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM1  Turn off FM1, verify doors are open, remove FM1  Turn off FM1, verify doors are open, remove FM1  Turn off FM1, verify doors are open, remove FM1	22			±50 °C	Start hat ramp
34 T0 +	33			+50 C	Start not ramp
36  T0 + RT Turn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM1  Turn off FM1, verify doors are open, remove FM1  T0 + RT End test FM1	3/1			+50 °C	Temperature-time bake-out for 48 h
35 T0 + RT Turn off FM1, return to RT, re-pressurize, open chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM1 36 T0 + RT End test FM1	J <del>-1</del>			1.30 C	Tomperature-time bake-out for 40 ff
chamber, turn on FM1, perform CPT after TV, turn off FM1, verify doors are open, remove FM1  TO + RT End test FM1	35			RT	Turn off FM1_return to RT_re-pressurize_open
off FM1, verify doors are open, remove FM1  TO + RT End test FM1			-		
36 T0 + RT End test FM1			[ ]		
	36		T0 +	RT	
			88		

Repeat this sequence replacing FM1 by FM2.